



# ग्रामपंचायत दरोडी ता.पारनेर जिल्हा .अहमदनगर


## दाखला


### (इतर योजनेत समाविष्ट व मंजूर नसल्याबाबतचा)

गटविकास अधिकारी(ऊ.श्रे) पंचायत समिती,पारनेर व उप अभियंता (सा.बां.) उपविभाग,पारनेर यांच्याकडून दाखला देण्यात येतो कि, मौजे दरोडी तालुका - पारनेर स्मशानभूमी सुधारणा अंतर्गत उर्वरित स्मशानभूमी सुधारणा करणे अंतर्गत मौजे दरोडी स्मशानभूमी सुशोभिकरण करणे .हे काम इतर योजनेत मंजूर नसून कोणत्याही योजनेत प्रस्तावित नाही. सदरचा दाखला जनसुविधा विशेष अनुदान योजने अंतर्गत प्रस्ताव काम मंजूर होणे कामी दिला आहे

स्थळ :- पारनेर

दिनांक: २६/०५/२०२३

  
ग्रामसेवक  
ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

  
अध्यक्ष  
ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

# ग्रामपंचायत दरोडी

ता.पारनेर जिल्हा .अहमदनगर



## जागा निर्वाद असलेबाबत प्रमाणपत्र

सरपंच ग्रामपंचायत दरोडी तालुका- पारनेर. यांच्या कडून मागणी करण्यात येते की , ग्रामपंचायत दरोडी साठी जनसुविधा विशेष अनुदान योजने अंतर्गत सुचविलेली कामे या योजने मधून स्मशानभूमी सुधारणा करणे अंतर्गत मौजे दरोडी स्मशानभूमी सुशोभिकरण करणे.मंजूर झाल्यास सदर कामासाठीची जागा निर्वाद आहे

सदर दाखला जनसुविधा विशेष अनुदान योजने अंतर्गत सुचविलेले कामे प्रस्ताव करिता दिला असे.

स्थळ :- पारनेर

दिनांक: २५ / ५ / २०२३

  
ग्रामसेवक

ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

  
सरपंच

ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

# ग्रामपंचायत दरोडी



ता. पारनेर जिल्हा .अहमदनगर

## मंजूर निधी पेक्षा वाढीव निधील खर्च प्रमाणपत्र

सरपंच ग्रामपंचायत दरोडी तालुका- पारनेर. यांच्या कडून मागणी करण्यात येते की , ग्रामपंचायत दरोडी साठी जनसुविधा विशेष अनुदान योजने अंतर्गत सुचविलेली कामे या योजने मधून मौजे दरोडी स्मशानभूमी सुशोभिकरण करणे.ह्या कामास मंजूर निधी पेक्षा जास्त निधी लागल्यास ग्रामपंचायत खर्च करण्यास तयार आहे.

सदर दाखला जनसुविधा विशेष अनुदान योजने अंतर्गत सुचविलेले कामे प्रस्ताव करिता दिला असे

स्थळ :- पारनेर

दिनांक: २४/१५ /२०२३

  
ग्रामपंचायत

ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

  
सरपंच

ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

# ग्रामपंचायत दरोडी ता.पारनेर जिल्हा .अहमदनगर



## इतर योजने मधून मंजूर नसले बाबत

सरपंच ग्रामपंचायत दरोडी तालुका- पारनेर. यांच्या कडून मागणी करण्यात येते की , ग्रामपंचायत दरोडी साठी जनसुविधा विशेष अनुदान योजने अंतर्गत सुचविलेली कामे या योजने मधून स्मशानभूमी सुधारणा करणे अंतर्गत मौजे दरोडी स्मशानभूमी सुशोभिकरण करणे.हे काम इतर कोणत्याही योजनेतून मंजूर नसून प्रस्तावित नाही.सदर दाखला जनसुविधा विशेष अनुदान योजने अंतर्गत सुचविलेले कामे प्रस्ताव करिता दिला असे

स्थळ :- पारनेर

दिनांक: 28/04/2023

  
ग्रामसेवक

ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

  
सरपंच

ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

# ग्रामपंचायत दरोडी



ता.पारनेर जिल्हा .अहमदनगर

## देखभाल दुरुस्ती प्रमाणपत्र

सरपंच ग्रामपंचायत दरोडी तालुका- पारनेर. यांच्या कडून मागणी करण्यात येते की , ग्रामपंचायत दरोडी साठी जनसुविधा विशेष अनुदान योजने अंतर्गत सुचविलेली कामे या योजने मधून स्मशानभूमी सुधारणा करणे मौजे मौजे दरोडी स्मशानभूमी सुशोभिकरण करणे.हे काम मंजूर झाल्यास सदर कामाची देखभाल दुरुस्ती करण्यास ग्रामपंचायत दरोडी तयार आहे .सदर दाखला जनसुविधा विशेष अनुदान योजने अंतर्गत सुचविलेले कामे प्रस्ताव करिता दिला असे

स्थळ :- पारनेर

दिनांक: २४/०५/२०२३

  
ग्रामसेवक

ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

  
सरपंच

ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

# ग्रामपंचायत दरोडी ता.पारनेर जिल्हा .अहमदनगर



## मागणी पत्र


सरपंच ग्रामपंचायत दरोडी तालुका- पारनेर. यांच्या कडून मागणी करण्यात येते की , ग्रामपंचायत दरोडी साठी जनसुविधा विशेष अनुदान योजने अंतर्गत स्मशानभूमी सुधारणा अंतर्गत मौजे मौजे दरोडी स्मशानभूमी सुशोभिकरण करणे.काम मंजूर झाल्यास सदरचे काम करण्यास ग्रामपंचायत दरोडी तयार आहे सदर दाखला जनसुविधा विशेष अनुदान योजने अंतर्गत सुचविलेले कामे प्रस्ताव करिता दिला असे.

स्थळ :- पारनेर

दिनांक:- 28/04 /2023


  
ग्रामसेवक

ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

  
सरपंच

ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

# ग्रामपंचायत दरोडी ता.पारनेर जिल्हा .अहमदनगर



मासिक सभा दि २७/५/२०२३ ठराव नं. १२ ची नक्कल

विषय नं. १२ :- विकास कामाबाबत चर्चा करणे.

ठराव नं. :- १२

सदर विषयावर बोलताना सरपंच म्हणाले कि, आपल्या गावातील स्मशान भूमीमध्ये अंत्यविधी होत असताना ते बाजूला असलेल्या लोकांना दिसते. त्यामुळे स्मशानभूमी मध्ये मौजे दरोडी येथे मौजे दरोडी स्मशानभूमी सुशोभिकरण करणे करणे. हे काम गरजेचे आहे म्हणून स्मशानभूमी सुधारणा करणे अंतर्गत स्मशानभूमीत मौजे दरोडी स्मशानभूमी सुशोभिकरण करणे आहे व त्या कामाचा प्रस्ताव देणे. त्यावर सभेने जनसुविधा विशेष अनुदान योजने अंतर्गत (लोकप्रतिनिधी यांनी सुचविलेले कामे) पुढील कामे सुचविले आहेत.

१) मौजे दरोडी स्मशानभूमी सुशोभिकरण करणे .

मा. सरपंच यांनी मांडलेला विषय अंत्यत गरजेचा असल्याने त्यास आजची सभा सर्वानुमते मंजुरी देत आहे.

सूचक : श्री. अनिल लक्ष्मणपावडे

अनुमोदक : सौ. जयश्री दिनेश चौगुले

ठराव सर्वानुमते मंजूर

ग्रामसेवक

ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

सरपंच

ग्रामपंचायत दरोडी,  
ता.पारनेर, जि.अहमदनगर

Ahmednagar Zilla Parishad  
ESTIMATE

Section Estimate No.

Fund Head

Major Head

Minor Head

Service Head

Departmental Head

Jansuvidha

2022-23

Estimate framed in the Office of the Executive Engineer,  
Zilla Parishad/Dy. Engineer, Zilla Parishad - Sub Division - Parner P.W. Ahmednagar of the probable  
expenses that will be incurred in

Name of work :- Development Smashanbhumi Premises at <sup>DARODI</sup> ~~Jawala~~ Tal. Parner, Dist.  
Ahmednagar

Rs. 1000000.00

Administratively approved under

No.

Dated

Technically sanctioned under

No.

Dated

Estimate prepared by *Shri. A.V. Jagdale Sect. Engineer, Z. P. P.W. Sub Div. Parner*

and checked by *Shri. P. B. Dhupad, Sectional Engineer, Z. P. P.W. Sub Div. Parner*

GENERAL DESCRIPTION

Daxodi

ime of work :- Development Smashanbhumi Premises at ~~Jayanta~~ Tal. Parner, Dist. Ahmednagar

### RECAPITULATION SHEET

Estimated Cost	Rs.	825143.00
		<hr/>
Total	Rs.	825143.00
Add 18.00 % GST		148525.74
Add Royalty charges	Rs.	20986.24
Add insurance 0.50 % charges	Rs.	4125.72
Add Contengency charges	Rs.	1219.31
		<hr/>
Total Amount	Rs.	1000000.00
Say	Rs.	1000000.00

97

Daxodi

ame of work :- Development Smashanbhumi Premises at ~~Jawala~~ Tal. Parner, Dist. Ahmednagar

ABSTRACT SHEET

Quantity	Item of work	Rate	Unit	Amount
12.02	Item no 1 :Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means	207.00	Cum	2488.14
11.34	Item no 2 :Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Mechanical Means	227.00	Cum	2574.18
0.151	Item no 3 : Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	89703.00	MT	13563.09
6.87	Item No 4 : Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand	5788.42	Cum	39766.45
30.24 29.82	Item No 5 : Providing cast in situ / ready mix M10 grade cement concrete for head walls of CD work / retaining walls etc. including necessary form work, compaction, finishing and curing etc. complete. (with reversible drum type mixer/ concrete batch mix plant (pan mixer) with SCADA with fine aggregates of required specifications ( VSI sand finely washed etc ), cement 4.40 bags/cumt)	8675.42	Cum	262344.70 259159.70
1.55	Item no. 6: Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.	7986.28	Cum	12378.73
3.60	Item no. 7: Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains	639.07	sqm	2300.65

Quantity	Item of work	Rate	Unit	Amount
3.60	Item no. 8: Providing and applying two coats of water proof cement paint of approved manufacture and of approved colour to the plastered surfaces including scaffolding if necessary, cleaning and preparing the surface, watering for two days etc. complete.	79.00	sqm	284.40
287.00 366.8	Item no. 9: Providing and fixing heavy duty inter locking concrete Coloured paving blocks of 80 mm thickness of having a strength of 300 Kilogram/Sq.cm. of approved quality and shape on a bed of crushed sand of 25 to 30 mm thick including skirting joints and cleaning etc. complete	1401.00 1096.00	sqm	402087.00
77.25	Item no.10 : Providing and fixing corrugated galvanised iron sheets of 0.63mm thick (24 B.W.G.) for roofing without wind tiles including fastening with galvanised iron screws and bolts, lead and bitumen washers as per drawing etc. complete.(Weight of 5.5 Kilogram/sq.m.).	870.00	sqm	67207.50
1.00	Item no 11 :Providing and fixing board displaying information, such as 'Name of work, Tender cost, Name of Contractor, Work completion and liability period etc', having rectangular shape of 1.20m x 0.90m size made out 18 gauge (1.25mm) thick mild steel sheet painted with one coat of Zinc chromate stoving primer and two coats of enamel paint on front side and grey stove enamel on back side and border / messages / symbols etc. with approved colour shade paint complete, on M.S.angle of size 35 x 35 x 3 mm frame with properly cross braced M.S. angles of size 35mmx35mmx3mm duly painted including Two M.S. angle iron posts of size 65 mm x 65 mm x 6 mm, 3.65 m long painted with alternate black and white bands of 25 cm width including all fixtures etc.and fixing the boards in 1:4:8 concrete block of size 60 cm x 60 cm x 75 cm including, excavation, refilling, transportation, and labour etc complete. Spec. Number As directed by Engineer in Charge	9963.00	No	9963.00
500.00	Item no 12 :Providing and fixing H.D.P container one piece moulded water tank made out of high density polythylar and built corrugated inclusive of delivery up to destination hoisting and fixing of accessories such as inlet,outlet overflow pipe inclusive of all tanks capacity between 200 to 1000 liters	14.00	No	7000.00
2.00	Item no 13 :Test - paving block 80 mm - Compressive Strength .	2495.00	No	2495.00 4990.00
2.00	Item no 14 :Test - c c cube	690.00	No	<del>690.00</del> 1380.00
			Total Rs.	825142.84
		Say	Rs.	825143.00

21/2/27  
Junior / Sect.Engineer

Deputy Engineer  
Z.P.P.W. Sub Div. Parner

Name of work :- Development Smashanbhumi Premises at ~~Jawate~~ <sup>Davadi</sup> Tal. Parner, Dist. Ahmednagar

### MEASUREMENT

Item of work	No	Length	Breadth	Height	Quantity	Unit
Item no 1 :Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means						
for Retaining Wall	1	42.00	0.90	0.30	11.34	
otta	1	1.50	1.50	0.30	0.68	
					<b>12.02</b>	<b>Cum</b>
Item no 2 :Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Mechanical Means						
for Retaining Wall	1	42.00	0.90	0.30	11.34	
					<b>11.34</b>	<b>Cum</b>
Item no 3 : Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.						
as per item4	30.24 cum	5.00 kg/cum			151.20 kg	
for temperature steel					<b>0.151</b>	<b>MT</b>
Item No 4 : Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand						
for Retaining Wall found.	1	42.00	0.90	0.10	3.78	
otta found.	4	1.50	0.45	0.10	0.27	
otta floor	1	1.50	1.50	0.10	0.23	
for paving locking smashan	2	14.00	0.25	0.15	1.05	
	2	20.50	0.25	0.15	1.54	
					<b>6.87</b>	<b>Cum</b>
Item No 5 : Providing cast in situ / ready mix M10 grade cement concrete for head walls of CD work / retaining walls etc. including necessary form work, compaction, finishing and curing etc. complete. (with reversible drum type mixer/ concrete batch mix plant (pan mixer) with SCADA with fine aggregates of required specifications ( VSI sand finely washed etc ), cement 4.40 bags/cumt)						
for Retaining wall	1	42.00	0.60	1.20	30.24	
					<b>30.24</b>	<b>Cum</b>
Item no. 6: Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.						
otta	2	2.10	0.23	0.90	0.87	
	2	1.64	0.23	0.90	0.68	
					<b>1.55</b>	<b>Cum</b>

Item of work	No	Length	Breadth	Height	Quantity	Unit
Item no. 7: Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 Kilogram per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc. complete.						

otta	2	1.50		0.60	1.80	
	2	1.50		0.60	1.80	

3.60 sqm

Item no. 8: Providing and applying two coats of water proof cement paint of approved manufacture and of approved colour to the plastered surfaces including scaffolding if necessary, cleaning and preparing the surface, watering for two days etc. complete.

qty as per item no.

3.60

3.60 sqm

Item no. 9: Providing and fixing heavy duty inter locking concrete Coloured paving blocks of 60 mm thickness of having a strength of 300 Kilogram/Sq.cm. of approved quality and shape on a bed of crushed sand of 25 to 30 mm thick including skirting joints and cleaning etc. complete

in smashanbhumi

1	14.00	20.50			
---	-------	-------	--	--	--

287.00

287.00 sqm

Item no.10 : Providing and fixing corrugated galvanised iron sheets of 0.63mm thick (24 B.W.G.) for roofing without wind tiles including fastening with galvanised iron screws and bolts, lead and bitumen washers as per drawing etc. complete.(Weight of 5.5 Kilogram/sq.m.).

	2	7.50	3.65		
	2	7.50	1.20		
ridge	1	7.50	0.60		

54.75

18.00

4.50

77.25 Cum

Item of work	No	Length	Breadth	Height	Quantity	Unit
Item no 11 :Providing and fixing board displaying information, such as 'Name of work, Tender cost, size made out 18 gauge (1.25mm) thick mild steel sheet painted with one coat of Zinc chromate stoving primer and two coats of enamel paint on front side and grey stove enamel on back side and border / messages / symbols etc. with approved colour shade paint complete, on M.S. angle of size 35 x 35 x 3 mm frame with properly cross braced M.S. angles of size 35mmx35mmx3mm duly painted including Two M.S. angle iron posts of size 65 mm x 65 mm x 6 mm, 3.65 m long painted with alternate black and white bands of 25 cm width including all fixtures etc.and fixing the boards in 1:4:8 concrete block of size 60 cm x 60 cm x 75 cm including, excavation, refilling, transportation, and labour etc complete. Spec. Number As directed by Engineer in Charge	1				1.00	1.00 No
Item no 12 :Providing and fixing H.D.P container one piece moulded water tank made out of high density polythylar and built corrugated inclusive of delivery up to destination hoisting and fixing of accessories such as inlet,outlet overflow pipe inclusive of all tanks capacity between 200 to 1000 liters	500				500.00	500.00 lit
Item no 13 :Test - paving block 80 mm - Compressive Strength .	1				1.00	1.00 No
Item no 14 :Test - c c cube	1				1.00	1.00 No

  
 Junior Sect.Engineer


Name of work :- Development Smashanbhumi Premises at Jawala Tal. Parner, Dist. Ahmednagar

### ROYALTY STATEMENT

Sr.No.	Item	Quantity	Quantity Required		Total Qty for sand	Total Qty for HM/
			Sand	Rubble/Murum		
1	PCC 1:3:6					
2	Retaining wall M-10	6.87	0.470		3.23	
3	BBM in plinth	30.24	0.470	0.00	14.21	0.00
4	Sandface plaster 1:4	1.55	0.320	0.00	0.50	0.00
5	providing GI sheet	3.60	0.033	0.00	0.12	0.00
		77.25	1.000			77.25
Total Qty					18.06	77.25
Rate					237.37	216.18
Amt					4286.33	16699.91
Total Amt.					20986.24	

### CEMENT CONSUMPTION STATEMENT

Sr. No	Item of work	Quantity	Rate of Consumption	Total Cement Bags
1	PCC 1:3:6	6.87	4.40	30.23
2	Retaining wall M-10	30.24	4.40	133.06
2	BBM in plinth	1.55	1.58	2.45
2	Sandface plaster 1:4	3.60	0.25	0.90
				166.64 Bags

  
Junior / Sect.Engineer

  
Deputy Engineer  
Z.P.P.W. Sub Div. Parner

